BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/08/2020-21 Dated: 26-11-2020

APPROVED TENDER SCHEDULE –'B'

Item 07

Name of Work :-Improvements to roads and drains at Attur Village surrounding areas in ward no:03

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri R SHIVARAM	
				Rate	Rate in Words
1	KSRB 300-1 : Earthwork Excavation by manual means for roads, drains and similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per Engineer In-Charge.	Cum	1346.40	220.40	Two Hundred Twenty Paise Fourty Only
2	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials,labour, HOM curing, form works, scaffolding and centering complete as per Engineer in charge.	Cum	201.96	5509.33	Five Thousand Five Hundred Nine Paise ThirtyThree Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 Kgs with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, labor, HOM complete as per specifications do-Wall & Bottom thickness 15cm as per engineer in charge.	Cum	434.25	7189.42	Seven Thousand One Hundred EightyNine Paise FourtyTwo Only

	oviding T.M.T steel reinforcement for R.C.C ork including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications.	Tonne	28.23	65046.90	SixtyFive Thousand FourtySix Paise Ninety Only
5	Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:1.5:3 using graded granite jelly 20 mm and down size with steel reinforcement and pointing for joints 1: 3 cement mortor including form work lift charges, curing and concrete finished on both	Sqm	1098.00	2337.00	Two Thousand Three Hundred ThirtySeven Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.